Liquid Waste ARRA Scope of Work

Citizens Advisory Board Waste Management Committee

October 20, 2009

Presentation By Jean Ridley, P.E.

Federal Project Director Assistant Manager for Waste Disposition Projects Department of Energy Savannah River Operations Office



Purpose & Acronyms

- Provide information on the Liquid Waste American Reinvestment and Recovery Act Scope of Work
- Acronyms
 - ARRA American Reinvestment and Recovery Act
 - DWPFDefense Waste Processing FacilitySRRSavannah River Remediation, LLCSWDESett Weste Processing Facility
 - SWPF Salt Waste Processing Facility



Schedule Highlights

- SRR 180 Day Plan & ARRA Deliverables 10/20
- SRR Technical, Cost & Fee Proposal 11/16
- SRR Liquid Waste ARRA Performance
 Baseline
 1/20
- Agreement on Definitization of ARRA Work 2/24
- Execute Definitization Contract Modification 3/16



Funding & Jobs

- Funding \$200 M Total
 - \$100 M in FY2010
 - \$100 M in FY2011
- Separate Accounting/Reporting
- 480 jobs created/retained



SWPF Integration - Tank Farm Infrastructure for Feed Readiness

- Design and purchase 4 salt blend mixer pumps (Tanks 35,41,50, spare)
- Purchase 4 replacement mixer pumps (Tank 51)
- Design and effect modifications to tank top to support mixer/transfer pump installation and install one mixer pump (Tank 51)
- Radiation shielding for waste processing tank (Tank 50)
- Design and install chemical addition and transfer process piping
- Enhance Saltstone Facility waste feed storage capability
- Increase nitrogen tank capacity at DWPF



Tank Farm Infrastructure Improvements

- Replace computer control systems
- Replace underground steam system utility piping
- Replace chromate cooling water system utility piping
- Replace underground well water system utility piping
- Replace underground plant and instrument air system utility piping
- Replace condensate / overhead piping for 2H & 2F evaporators
- Relocate and install mixer pumps and refurbish tanks for cleaning prior to closure (Tanks 5 & 6)



Salt Waste Processing Improvements

- Replace Saltstone Facility grout piping, hopper, hopper agitator, and pulsation damper systems
- Purchase replacement Saltstone Facility air compressor, mixers, vault cameras, and grout pump systems

Sludge Processing Improvements

- Tank 13 mixing, transfer, cooling, and ventilation systems installed to support sludge feed preparation
- Install bubblers in DWPF melter
- Upgrade support equipment to accommodate DWPF melter bubblers



DWPF Infrastructure Improvements

- Refurbish cooling tower
- Replace argon tank
- Replace safety computer control systems
- Replace ventilation system (Zone 2)
- Purchase replacement electro-mechanical manipulators
- Purchase replacement bellows for DWPF melter

Safety Improvements

- Install computer-based security badge accountability system at Saltstone Facility
- Install system to divert surface water for sufficient drainage for Vault 4



- Work Safely
- Execute Scope
- Create & Report Jobs
- Full Cost Accounting

