

# Defense Waste Processing Facility Update







Savannah River Site Citizens Advisory Board SRR-DWP-2015-00005




April 2015






### **Liquid Waste Operations Overview**






### **SRS Liquid Waste Program**





## **An Integrated System**






# **Waste Processing**

We do the right thing.

### Removing Sludge Waste from Tanks



Water and Liquid Waste



### Immobilize Waste for Disposal



#### **Defense Waste Processing Facility**

- Very little of waste volume goes here, but almost all curies dispositioned at DWPF
- World's largest vitrification plant
- Over 3,900 canisters filled.
   DWPF has poured since 1996 more than 13.5 million pounds of glassified waste
- Entire 37 million gallons of waste in the tanks awaiting disposition has about 295 million curies of radioactivity




#### Interim Storage of Canisters

- DWPF Glass Waste Storage Buildings
  - GWSB 1 contains 2,244 canisters
  - GWSB 2 currently contains over 1,250 canisters (capacity for 2,340)
- Underground reinforced concrete vaults
- Seismically qualified
- Designed for safe interim storage



# **Vitrification Process**





### **DWPF Production**

- Facility currently in planned outage to upgrade infrastructure
- On schedule to produce desired number of canisters this year
- Canister Production Rate Based on System Plan 19
  - FY15 156
  - FY16 136 with 4 month melter outage
  - FY17 168
  - FY18 160 with 4 month outage for transition to SWPF operation
  - FY19 276
  - Beyond 276
- Canisters Produced To Date (March 12, 2015)
   3954
- Estimated Total Canister Production 8582
- Canisters Produced (% of Total) 46%
- Canister Production Exceeds Canister Storage in FY19



We do the right thing.

# GWSB #1 Interim Canister Storage – Double Stack




# Supplemental Canister Storage Options

- No 3<sup>rd</sup> Glass Waste Storage Building (GWSB) (~ \$130 million)
  - Large upfront cost & future D&D cost
- Glass Waste Storage Project (GWSP) Being Developed to Provide
  - Supplemental Canister Storage in above ground storage containers similar to commercial SNF storage
  - Loading Station for SCT transfer of canister to storage containers
  - Storage pad for storage containers
  - Storage containers procured to support canister production
  - Allow future construction of canister transportation capabilities
- Interim Canister Storage Required Until GWSP Complete
  - With Double Stack of Canisters in GWSB #1
    - GWSB#1 Capacity Increased from 2,254 to 4,508
    - GWSBs Capacity Increased to 6,848 providing space through FY 26
    - Still need space for 1,734 more canisters



# Interim Canister Storage - Double Stack Concept for GWSB1




- Two canisters per location (vs. one can per location)
- Lower canister on support on vault floor (vs. cross bar support 3' off floor)
- Upper canister placed directly on top of lower canister
- Upper canister extends into operating deck floor, but remains below grade
- Shield plug redesigned for equivalent radiological protection



## Glass Waste Storage Building 1 Vault


- Inside vault looking across rows of canister supports
- Inside canister storage location
  - Minimum Opening in floor is 27 inch ID
  - Cross Bar Assembly is 1 ½ inch x
     3 inch galvanized carbon steel
     bars
  - Cross Bar Assembly~ 18 ft down with 30 inch OD
  - 2 sets of guides (3 tabs each) to guide canisters
  - Bottom guides sit 5 inches above cross bar assembly







# **Proposed Modifications**





# **Technical Evaluation Summary**

- Heat Model supports canisters produced to date and future sludge batch forecast
- Seismic/Structural calculations support adequate margin for static and seismic performance category and canister integrity
- Cutting tool technology exists: prototype and mockup in progress
- Radiological model/calculations supports canisters produced to date and future sludge batches
  - Design basis < 5 mrem/hr</li>
  - Implemented with new plug design and canister tracking
- Radiological calculations confirm dose rates during modification w/o completely emptying vault



# Technical Evaluation Summary Cont'd

We do the right thing.

# Major Modification Evaluation Approved – Not a major modification

- No new SSCs required and modifications are not complex
- Does not introduce new hazards or change existing Hazard Category (HC 2)
- DSA change to update configuration change

### Safety Basis Strategy Approved

- Canister Double Stack activities will not alter the Hazard Category
- Increase in MAR evaluated and preliminary consequences do not exceed consequences reported in DWPF FSAR for NPH events
- Modifications to SS vault and canister support designed to PC-2 and meet safety function
- Anticipate negative USQE for new plug



# Technical Evaluation Summary Cont'd

We do the right thing.

### PCHA Approved

- Identified no new events that could exceed the EGs for Offsite, CW, or FW
  - No new SC or SS controls
- No new DID/ITS controls or SAC identified
- Events credit Hazard Abatement controls

### Modified Fire Hazard Analysis Approved

- Identified additional controls
  - Building controls to mitigate fire risk
  - Cutting Tool Controls to mitigate fire risk
  - Fire Department Considerations
- Requires Equivalency for GWSBs to be revised



## **Canister Storage Summary**

- Technical Evaluation Supports Double Stacking GWSB1
- Use Interim Canister Storage Double Stack to Bridge Canister Storage Gap
- Increases GWSB1 capacity to 4508 canisters
- Provides adequate storage through FY26



## **Acronym List**

- DWPF: Defense Waste Processing Facility
- SWPF: Salt Waste Processing Facility
- ARP: Actinide Removal Process
- MCU: Modular Caustic Side Solvent Extraction Unit
- BWRE: Bulk Waste Removal Efforts
- GWSB: Glass Waste Storage Building
- LPPP: Low Point Pump Pit
- SRAT: Sludge Receipt and Adjustment Tank
- SME: Slurry Mix Evaporator
- MFT: Melter Feed Tank
- SCT: Shielded Canister Transporter
- GWSP: Glass Waste Storage Project
- MAR: Material at Risk
- SNF: Spent Nuclear Fuels
- SSCs: Structures, Systems and Components

- USQE: Unreviewed Safety Question
- FSAR: Final Safety Analysis Report
- NPH: Natural Phenomenon HazardsDID: Defense in Depth
- ITS: Equipment Important to Safety
- EG: Evaluation Guidelines
- CW: Collocated Worker
- FW: Facility Worker
- SS: Safety Significant
- SC: Safety Class
- FY: Fiscal Year
- SAC: Specific Administrative Controls
- MREM: One thousands of a REM
- REM: Roentgen Equivalent Man
- HLW: High Level Wastes
- D&D: Decommissioning and Demolition