

Liquid Waste (LW) Program Strategic Vision

Soni Blanco, DOE Waste Disposition Program Director Mike Borders, SRMC Optimization and Integration Director

November 2022

SAVANNAH RIVER SITE • AIKEN • SC • WWW.SRS.GOV

Liquid Waste Program

- Retrieve, process, treat, and dispose of legacy tank waste
- 43 active waste tanks, 35 Mgals of highactivity radioactive waste
- Four End States
 - Operational Tank Closure
 - Vitrified high-level waste canisters in Glass Waste Storage Buildings (GWSBs) 1 & 2
 - Low-level waste in Saltstone Disposal Units
 - Deactivate and flush operating facilities to enable safe setup for decommissioning activities

Key processing and treatment facilities

- Defense Waste Processing Facility (DWPF)
- Salt Waste Processing Facility (SWPF)
- Saltstone Production Facility (SPF)
- Saltstone Disposal Units (SDUs)



Liquid Waste Path



SAVANNAH RIVER SITE . AIKEN . SC . WWW.SRS.GOV

End State Contract - Task Order Schedule



- Purpose of End-State Contract
 - Complete Liquid Waste (LW) Mission in 15 Years
 - A holistic LW System
- SRMC Technical Approach
 - Focus on Early Reduction of Most Significant Risk
 - Optimized Processing Approach
- LW System Planning
 - Guided by a strong, established, effective Regulatory Model meeting expectation to engage Regulator Involvement
 - Realignment of Regulatory Approach

Focused on Risk Reduction

DOE and SRMC are committed to partnering to seamlessly and safely transform SRS liquid waste operations to an end state-driven culture of completion



Five primary initiatives in order to meet the goals of the DOE's end state contracting model

- Liquid waste system optimization and improvement
- Services review and cost reduction
- Work process improvement
- Enhanced workforce / small business utilization
- Risk-based, end-state regulatory partnering



DOE - Department of Energy

6

• Focus High Curie 1st

- Focus on Risk/Curie Reduction
- Focus on Optimizations & Increase Throughput
- Optimize timing of Next Generation Solvent (NGS)
 Implementation
- Focus on Getting Out of Old-Style Tanks in Water Table
 - Evaluate near term use of TCCR (Tank Closure Cesium Removal)

Begins with Partnering

SRS Liquid Waste Program

Common Values and Goals (2022 – 2037)

June 29, 2022

VALUES

- 1. Maintain transparency with open communication between regulators, DOE, and the contractor on program progress, and significant emerging issues.
- 2. Ensure DOE's strategy and plans are subject to stakeholder engagement and input, including SCDHEC permitting processes, and CERCLA, as appropriate.
- 3. Maximize the amount of curies (especially long-lived radionuclides) vitrified and ready for ultimate disposal out of state.
- 4. Limit disposal of curies onsite at SRS so that residual radioactivity is as low as reasonably achievable.

GOALS (in priority order)

- 1. Reduce risk to the environment by removing waste and closing tanks with a goal of completion of the liquid waste program by 2037.
- 2. Reduce operational and environmental risk by aggressively removing curies from the waste tanks.
- 3. Reduce operational and environmental risk by optimizing operations to minimize liquid waste program total life cycle.
- 4. Complete waste removal and subsequent grouting of all waste tanks and ancillary structures with a risk-based priority order: first to tanks in the water table, followed by F Tank Farm tanks, followed by remainder of waste tanks, followed by ancillary structures, recognizing the potential for future emergent conditions or opportunities. CERCLA - Comprehensive Environmental Response, Compensation, and Liability Act
 SCDHEC - South Carolina Department of Health and Environmental Control

1. LW Program Completion by 2037

- Enhanced System Modeling (DBD) in Progress
- System Plan Rev 23 submission to DOE for review in December 2022



2. Removing Curies

- Most recent Liquid Waste System Plan (Rev. 22) shows curies removed on a steady pace
- That changes with the new strategy

×.	Curies removed on	Batch Preparation Details			
	an	Batch	Na (M)	Ci/gal	To TK 49
	accelerated pace	B5	6.9	2.5	10/2022
		B6	7.5	2.0	2/2023
		B7	6.4	1.6	11/2022
*	Operational closure on tanks with the greatest risk	B8	6.9	2.5	5/2023
		B9	6.9	2.3	8/2023
		B10	6.9	2.5	11/2023
		B11	6.9	2.2	1/2024
		B12	6.9	1.8	3/2024
		B13	7.0	1.5	5/2024
		B14	7.0	1.3	7/2024
		B15	7.0	1.7	9/2024
		B16	7.0	1.4	11/2024
		B17	6.9	1.5	1/2025
		B18	7.0	1.5	3/2025
		B19	6.9	1.4	6/2025



Curies/Gallon: ~0.5 > 1.3 - 2.5 Sodium Molarity: > 6.44

2. Removing Curies



3. Optimizing Operations - Minimize Life Cycle

- Objective
 - Increase process attainment & availability
 - Then focus on throughput ramp up
 - Implement NGS once filtration is no longer limiting



3. Optimizing Operations - Minimize Life Cycle



SAVANNAH RIVER SITE . AIKEN . SC . WWW.SRS.GOV

4. Complete Waste Removal and Grouting of All Waste Tanks and Ancillary Structures



SAVANNAH RIVER SITE • AIKEN • SC • WWW.SRS.GOV

14

Completed TCCR Demo > Focus on SWPF

- TCCR was utilized when it was accelerating getting out of old-style tanks in water table
- Implemented as a mitigation factor with SWPF delays
- SWPF can now further accelerate getting out of old-style tanks in the water table
- TCCR may be considered in the future in more cost-effective applications



Ne	w Plan – Art of the Possible	Existing Plan
202	/R & Heel Removal complete by end of 24 from Tanks 9, 10, 11 & 15 and in idge Batch 12	BWR Complete • Tank 9 – FY26 Heel Removal Complete • Tank 9 – FY27 • Tank 10 – FY28 • Tank 11 – FY28 • Tank 15 – FY22
Tan	 hks 9,10,11, & 15 Enter Closure process in 2025 Grout complete in 2027 	Grout Complete

Risk/Curie Reduction Then Tank Closure



SAVANNAH RIVER SITE . AIKEN . SC . WWW.SRS.GOV

- Major Infrastructure in Place to Complete This Mission
- Focus Efforts on Risk Reduction
- Everything Evaluated Through the Lens of Does It Support & Align to "Finish in 15"
- Invest More, Early on Integrated Operations, Optimizations, and Waste Removal
- Opportunities on Back End
 - Accelerated Throughput with Lower Curie Feed
 - Isolate Close/Grout Tanks More Efficiently and at Less Cost

