

# End Stream Delivery (ESD) Optimization & Improvements

Rodney Blackmon  
ESD Facility Manager, SRMC

7/30/2024






- **End Stream Delivery within the Liquid Waste System**
  - Combining two facilities – A “Power as One” Organization
- **The Optimization Challenge**
- **Increasing Reliability**
- **Continuous Improvements**
- **Take Aways**



## SRS Liquid Waste Facilities





# ETF + SS = End Stream Delivery

- **Power as One: 2 Facilities, 1 Organization**
  - Name derived from Oil and Gas industry
  - Tank Farm (upstream); DWPF & SWPF (midstream) and Saltstone and Effluent Treatment Facility (end stream)
  - Delivery → mission complete as early as possible with a lower cost
- **Build Reliability using:**
  - Complementary operational cadence
  - Shift staffing
  - Eliminated need to hire 4th shift for SS
- **ESD placed under SWPF Organizationally**
  - Combine into standing Directorate
  - Utilize SWPF support organizations
  - Optimizes SWPF direct feed



ETF – Effluent Treatment Facility  
SS – Saltstone  
DWPF – Defense Waste Processing Facility  
SWPF – Salt Waste Processing Facility  
ESD – End Stream Delivery



## Treat wastewater to meet discharge limits for safe release to the environment

- **SCDES permitted facility**
- **Treats industrial water from contributing SRS facilities**
- **Discharged to Upper Three Runs Creek outfall**

SCDES – South Carolina Department of Environmental Services






## Immobilize Decontaminated Salt Solution (DSS) into Grout

- **Take in DSS from SWPF (either Tank 50 or direct)**
- **Mix dry feeds with DSS**
- **Send grout mixture to Saltstone Disposal Units**





# Saltstone Process



★ = Optimization Item

SDU – Saltstone Disposal Unit




- **SWPF Tie-ins in 2020**
- **~2-3x Production increase since SWPF came on-line**
- **Climb to Nine requires ~3x improvement**
- **Series of improvements in anticipation of the Climb to Nine effort**



# Using Tank 50 (Step 1)


- Most common route to date
- Provides greatest de-coupling from Saltstone
- Most traffic on the transfer highway





# Using Tank 50 (Step 2)

- Most common route to date
- Provides greatest decoupling from Saltstone
- **Most traffic on the transfer highway**





# Direct Transfer

- Most efficient use of the transfer lines
- Requires Operational Cadence





# Control Room Consolidation

- **Brings Effluent Treatment Facility controls together with Saltstone**
- **Single Shift Manager has command and control of both facilities**
- **Expanded roles for Control Room Operators**
- **Dedicated Maintenance and Support staff for both facilities**
- **Supports the complementary operational cadence**
- **Developing ESD Simulator adding ETF model to existing Saltstone**




ESD – End Stream Delivery  
ETF – Effluent Treatment Facility



# 299-H Mixer Rebuilds

- Previously rebuilt Saltstone mixer in process room
- 2+ weeks or more to rebuild in place with significant labor
- Rebuilding in 299-H allows the rebuild to take place while processing continues
- “Fly-in”/“Fly-out” methodology provides greater than 50% reduction in rebuild duration





# Dry Feed Delivery Optimization

- **Expanded parking for dry feed trailers**
- **Dedicated lead driver for off-load and scheduling**
- **Expanded delivery hours**
- **Solid Vendor support and relationship**
- **Production requires ~1 truck per hour**






## Dry Feeds Upgrade

- Refurbish membrane in silo and air slides for easier unloading
- Re-pipe air system to reduce clogging
- New process air compressors to allow 3 trucks to unload simultaneously
- Mods underway to unload a 4<sup>th</sup> truck simultaneously







## Cement-Free Operation



|      |         |      |        |        |
|------|---------|------|--------|--------|
| Old: | (Spare) | Slag | Flyash | Cement |
| New: | Flyash  | Slag | Slag   | Flyash |



# Process Critical Equipment





- **End Stream Delivery is:**

- Safely reducing risks by combining two facilities into a single, Power as One organization
- Improving Reliability by optimization upgrades in dry feeds and Process Critical equipment
- Delivering increased throughput with cement free grout, strong vendor relationships, and direct transfer
- Continuously improving by use of 299-H and similar efforts to save time and improve the reliability of our equipment